



Finance
Purchasing Division
929 North Front
Street, 10th Floor
P O Box 1810
Wilmington, NC 28402-1810

910 341-7830
910 341-7842 fax
wilmingtonnc.gov
Dial 711
TTY/Voice

ADDENDUM NUMBER 1
10TH ST AND GRACE ST INTERSECTION IMPROVEMENTS
PAV-IH-0724
August 22, 2024

To all holders of PAV-IH-0724 Bid Documents: Please be advised of the following questions and responses:

Question 1:

Can the bid opening date be adjusted due to the Labor Day holiday?

Response 1:

The bid opening date has been changed to September 12th, 2024, at 3:00 PM. The location of the bid opening has not changed.

Question 2:

Can a line item be added to the bid schedule for construction surveying?

Response 2:

Yes, a line item has been added to the bid schedule for construction surveying. Construction surveying will be the responsibility of the contractor and will not be provided by the City of Wilmington.

Question 3:

Is a traffic control plan required?

Response 3:

Yes, a traffic control plan furnished by the contractor is required for the project. An example plan is already provided in the bid documents. The intersection may be closed to through traffic but must remain open for residents whose properties are serviced by driveways in the project area.

Question 4:

Can the units for the asphalt overlay line items be changed from square yards to tons?

Response 4:

Yes, the units for the asphalt overlay line items have been changed from square yards to tons.

Question 5:

What is the schedule for the project and what times are available to work?

Response 5:

The contractor shall complete all work in the contract within 90 calendar days from the date of beginning. Section TS-15.34 on page TS-15-12 in the technical specifications details the project work times. Please use the following link for additional information about work in City of Wilmington right-of-way: <https://www.wilmingtonnc.gov/Government/Departments-Divisions/Engineering/Right-of-Way-Permits>.

Acknowledge receipt of this Addendum in the space provided in the Proposal. Failure to do so may disqualify the Bidder.

Christine R. Karem, Sr. Contract Specialist
M/WBE Coordinator
Purchasing Division
END OF ADDENDUM ONE

Bid Schedule

Base Bid

Item No.	Item Description	Quantity	Unit	Unit Cost	Total Cost
1	Mobilization & General Requirements	1	LS		
2	Traffic Control	1	LS		
3	Construction Surveying	1	LS		
4	Erosion Control Measures	1	LS		
5	Tree Protection	3	EA		
6	Asphalt Pavement Demolition	1010	SY		
7	Curb Demolition	685	LF		
8	Miscellaneous Demolition	1	LS		
9	Tree Removal	3	EA		
10	Backfill Material	350	CY		
11	Fine Grading	1	LS		
12	Existing Asphalt Pavement Milling, Depth Varies (2" Min.)	1850	SY		
13	2" S9.5B Asphalt Pavement Overlay	185	TN		
14	Concrete Sidewalk	150	SY		
15	Curb Ramp	8	EA		
16	6" Concrete Curb	875	LF		
17	Driveway Turnout	2	EA		
18	Pavement Marking	1	LS		
19	Remove/Salvage/Reinstall Signage	1	LS		
20	12" Reinforced Concrete Pipe	5	LF		
21	18" Reinforced Concrete Pipe	10	LF		
22	Catch Basin w/ Frame, Grate, and Hood	2	EA		
23	Drop Inlet Frame and Grate	2	EA		
24	Existing Curb Inlet Top Replacement	1	EA		
25	Bioretention Cell Excavation	100	CY		
26	Bioretention Cell Media Mix	80	CY		
27	Bioretention Cell Outlet Control Structure	1	EA		
28	Bioretention Cell Sod Surface	285	SY		
29	Bioretention Cell Rip-Rap	6	CY		
30	Street Trees	3	EA		
31	Permanent Seeding, Fertilizing, Mulching	815	SY		
Total					

Alternate

Item No.	Item Description	Quantity	Unit	Unit Cost	Total Cost
ALT-1	Existing Asphalt Pavement Milling, 2"	1850	SY		
ALT-2	2" S9.5B Asphalt Pavement Overlay	185	TN		
ALT-3	Permanent Seeding, Fertilizing, Mulching (in lieu of Bioretention Cell)	125	SY		
Total					

Payment for structure installation shall constitute full compensation for all labor, equipment, tools, supplies and incidentals necessary to complete all items of work, including excavation and backfill necessary to construct the structure, compaction of sub grade, hauling, construction of fills and embankments, spreading, rolling, wetting and disposal of all surplus and unsuitable materials, as indicated on the drawings and specified herein.

TS-15.32 FINAL CLEANUP:

The Contractor shall clear all streets, curbs, gutters, driveways and other contract items of all dirt and debris before final inspection will be made. The City will not inspect the improved areas until they are cleaned. Failure by the City to perform final inspection if the areas are not cleaned shall not relieve the Contractor of any liquidated damages. No extra payment will be allowed for this cleaning. The cost of the cleaning shall be included in each item bid in the proposal.

TS-15.34 PROJECT WORK TIMES:

Unless requested in writing and approved by the City in advance, the Contractor shall not be allowed to perform construction activities on City recognized holidays, or before 7:00 a.m. or after 6:00 p.m. on weekdays.